



DRAFT QUOTE

Adam 20 Lemnos Place Titirangi

Date
30 Jun 2026

Expiry
21 Jul 2026

Quote Number
QU-0568

GST Number
085-857-223

J Naughton T/A Pristine
Gardens
1/44 Kelwyn Road
Kelston
Auckland 0602
NEW ZEALAND

Lawn levelling and retaining

Description	Amount NZD
Back Lawn Retaining Edge, Soil Levelling and Seeding Labour	5,328.75
Spray off existing lawn area with extra strength weedkiller.	
Install small timber retaining edge (400 high/ 2 x 200x50 retaining timber).	
Retaining edge to sit approximately 900 mm off the fence (or as close to the large tree near the entry fence as practical).	
Pull back low soil currently sitting against the fence and install polythene along the bottom of the fence to help protect it.	
Bring in new soil, shift with skid steer, finalise levels by hand with rakes and screeding, roll to compact, then spread lawn seed and fertiliser.	
Materials	2,870.00
200x50 H4 retaining timber	
100x100 H4 timber posts	
Concrete for post holes	
Fixings	
Polythene fence protection	
Lawn seed	
Starter fertiliser	
5.5 m³ Lawn mix (weed free so seed can go down straight away)	
Soil delivery / transport	
Skid steer	
\$2,870 including GST	
Optional Materials	0.00
Planting hedge row (Ficus Tuffi)	
Planting 1.2m Ficus Tuffi along fence line *note that this only goes up to pool*	

Description	Amount NZD
Ficus Tuffi 1.2m plants and labour to plant \$2,420	
Not included in quote only as a reference	
Water blast (if applicable) \$240 *not included in quote*	0.00
INCLUDES GST 15%	1,069.40
TOTAL NZD	8,198.75